BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

BBMP/2015-16/OW/WORK_INDENT19476/CALL-2

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/03/2015-16 Dated: 08-03-2016

Approved Tender Schedule - B

Item No 6

Name of Work: Improvement of roads and drains in B sector in Ward no 04 Yelahanka New Town Sub Division

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri N LOKANATHREDDY	
				Rate	Rupees in words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no141, PWD SR 2015-16)	Cum	170.2	80.66	Rupees Eighty and paise sixty six only
2	Removing B.S slab of drain and stacking (P.No 25 I.No 5.32)g	sqm	283.5	61.8	Rupees sixty one and paise eighty only
3	Refixing stone slabs of drains and pointing in CM(1:3)(P.No 25 I.No 5.33)	sqm	283.5	73.47	Rupees seventy three and paise forty seven only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms	sqm	121.5	643.22	Rupees six hundred forty three and paise twenty two only
5	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2015-16	Cum	170.2	71.23	Rupees seventy one and paise twenty three only
6	KSRRBM400-17,Providing, laying, spreading andcompacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site,laying in uniform layers with paver in sub base/base course on well prepared surface and compacting with vibratory roller to achieve the desired dencity complete as per specifications.MORTH Specification No.406(Item no20.18,Page no157 ,PWD SR 205-16)	Cum	41.25	1662.54	Rupees one thousand six hundred sixty two and paise fifty four only
7	KSRRB M500-6,Providing and applying primer coat with S.S.bitumen emulsion on prepared surface of granular base such as WBM,WMM including cleaning of road surfase and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH Specifications No502 (ITEMNO21.6,Page no157,PWD SR 2015-16)	sqm	750	31.42	Rupees thirty one and paise forty two only

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri N LOKANATHREDDY	
				Rate	Rupees in words
8	KSRRB M500-18.Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading,premixed with bituminous binder and filler,transporting the hot mix to work site.laying with a paver finisher to the required grade,levell and alignment,rollingwithsmoothwheeled,vibratoryandtandemrollers to achievethedesiredcompactionasperMORTHSpecificationclauseno508completeinallrespectscompleteaspers pecifications.using100120THcapacityH.M.P with sensor paver grading (35-40mm)with4.5%CRMB55grade(Itemno21.21.1,Pageno16D 2015-16)	Cum	22.5	8986.31	Rupees eighty thousand nine hundred eighty six and paise thirty one only
9	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications. Specification no KBS4.1,4.2 (Item no 4.3,Page no12,PWD SR 2015-16)	Cum	59.4	4917.9	Rupees four thousand nine hundred seventeen and paise ninty only
10	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work (PWD SR 2015-16, p.no13,no 4.11)	Cum	39.6	6012.17	Rupees six thousand twelve and paise seventeen only

N. Lokanatha Reddy

Signature of the contrator

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.